Buildiqo.ai

CIVIL ESTIMATION & STRUCTURAL BOQ REPORT

IS 456:2000 & IS 13920:2016 Compliant Engineering Takeoff • Date: 31 Oct 2026

REF: BQ-164605

Jurisdiction: Bengaluru, Karnataka

Bangalore Luxury Residence

Client: High Net Worth Client | Location: Bengaluru, Karnataka | Package: STANDARD PACKAGE | Structure: RCC Framed

PLOT & SITE GEOMETRY	CONSTRUCTED BUILT-UP (SBA)	PACKAGE RATE BENCHMARK
Dimensions: 55 ft × 55 ft	Total SBA (BUA): 6,050 sq.ft	Tier: Standard Package
Gross Plot Area: 3,025 sq.ft	Carpet Area (70%): 4,235 sq.ft	Agreed Rate: Rs. 2,250 / sq.ft
Area in Sq.Yards: 336.1 sq.yd	Floor Count: 2 Levels (G + 1)	GST Status: Statutory 18% Applicable
Orientation: North Facing	Typology: Independent Residential	Methodology: Deterministic IS 456

1. FINANCIAL & STATUTORY TAX SUMMARY

Financial Component		
Constructed Built-up Area (SBA / BUA)	Gross chargeable area across all levels	**6,050 sq.ft**
Selected Construction Package Tier	Comprehensive material & workmanship scope	**Standard Package**
Agreed Package Internal Base Rate	Pre-GST rate per sq.ft constructed area	**Rs. 2,250 / sq.ft**
Base Construction Cost (SBA × Package Rate)	6,050 sq.ft × Rs. 2,250 / sq.ft	**Rs. 1,36,12,500**
Statutory GST (18%)	Statutory tax on works contract (IS / GST Law)	**Rs. 24,50,250**
GRAND TOTAL ESTIMATED INVESTMENT	**Total all-inclusive contract investment**	**Rs. 1,60,62,750**
Effective All-Inclusive Cost per Sq.Ft	Comprehensive post-tax cost per sq.ft SBA	**Rs. 2,655 / sq.ft**

2. FLOOR-WISE AREA BREAKDOWN

#					
1	Ground Floor	2,117.5 sq.ft	3,025 sq.ft	9	50.0%
2	1st Floor	2,117.5 sq.ft	3,025 sq.ft	8	50.0%
	Total Constructed Coverage	**4,235 sq.ft**	**6,050 sq.ft**	**17**	**100.0%**

3. STRUCTURAL MATERIAL TAKEOFF (IS 456:2000 SPECIFICATIONS)

Material Category			
Reinforcement Steel Rebar	JSW Neosteel Fe 550D High-Ductility TMT (IS 1786)	**21.18**	Tonnes
Structural Grade Cement	UltraTech Super 53 Grade / PPC WeatherPro (IS 12269)	**2,541**	Bags (50kg)
Manufactured Sand (M-Sand)	Manufactured Double-Washed VSI M-Sand & P-Sand (IS 383)	**11,495**	Cu.Ft
Coarse Aggregate Jelly	Machine-Crushed Blue Metal Granite (20mm & 12mm)	**8,168**	Cu.Ft
Wall Masonry Units	Autoclaved Aerated Concrete (AAC) Lightweight Blocks	**7,563**	Blocks / Sq.Ft
Flooring & Wall Tiling	Double Charged 4x2 GVT Vitrified Tile Slabs	**4,531**	Sq.Ft
Waterproofing System	Dr. Fixit 2K Polymer Elastomeric Membrane (Toilets & Terrace)	**1.0**	Package (L.S)

4. STATUTORY & ENGINEERING COMPLIANCE NOTES

1. Structural Engineering Standards: Quantities calculated deterministically complying with IS 456:2000 (RCC), IS 13920:2016 (Ductile Detailing), and IS 1786:2008 (High Strength Deformed Steel Bars).

2. Geotechnical Soil Assumption: Safe Bearing Capacity (SBC) of foundation soil is benchmarked at 180-200 kN/m² for isolated pad footings. Deep piles or heavy rocky strata are evaluated via site borehole tests.

3. Comprehensive Workmanship Scope: Includes mechanized batch mixing, cube test verification (M25 grade 28-day compressive strength), immersion vibration, and statutory 14-day water curing protocols.

4. GST & Statutory Taxes: Statutory 18% Goods and Services Tax (GST) is itemized. External municipal sanction charges, betterment fees, and utility deposits (BESCOM / BWSSB) are client responsibilities.

Authoritative Legal Notice: This document is an algorithmic civil engineering and quantity surveying estimation issued by Buildiqo.ai. Final contractor agreement may vary based on architectural elevation detailing, approved structural drawings, and site-specific topography.