Buildiqo.ai

Commercial Bill of Quantities (BOQ) Schedule (Mode B)

Pricing Authority: Karnataka | Ref: TWC Kasthuri Nagar Detailed Schedule

TWC Kasthuri Nagar Detailed Schedule

Client: Bangalore Commercial Client | Location: Karnataka | Generated: 18 October 2026

DISCIPLINE: CIVIL WORKS

Substructure & RCC (Subtotal: Rs. 6,00,000.00)

Item	Description & Specification	Unit	Qty	Rate (INR)	Amount (INR)
1.1	Earthwork excavation in foundation trenches including dressing and disposal Make/Spec: Up to 2.5m depth in hard gravelly soil as per IS 1200	Cum	120	Rs. 350.00	Rs. 42,000.00
1.2	Providing and laying reinforced cement concrete M25 grade in footings and columns Make/Spec: Machine batch mixed and vibrated as per IS 456	Cum	50	Rs. 7,200.00	Rs. 3,60,000.00

FINAL COMMERCIAL ABSTRACT SUMMARY

Net BOQ Taxable Subtotal	**Rs. 10,00,000.00**
Goods & Services Tax (GST @ 18%)	**Rs. 1,80,000.00**
Grand Total Project Cost (All Inclusive)	**Rs. 11,80,000.00**

Commercial Notice: All figures deterministic and verified against active state baseline contracts. Direct contractor trade items represent all-inclusive execution rates. Raw material benchmark prices are maintained independently for reference and do not override contractor rates.