Buildiqo.ai

CIVIL ESTIMATION & STRUCTURAL BOQ REPORT

IS 456:2000 & IS 13920:2016 Compliant Takeoff • Date: 18 Oct 2026

Green Villa Estate

Client: Maaz Ayoob | Location: Bengaluru, Karnataka | Tier: STANDARD PACKAGE | Ref: BQ-200264

Plot Dimensions: 55 ft × 55 ft
Gross Plot Area: 3,025 sq.ft (336.1 sq.yd)
Carpet Area (70% Basis): 2,117.5 sq.ft
Constructed Built-up Area (SBA): 1,800 sq.ft
Floor Configuration: 2 Floor(s) (G + 1)
Selected Package Rate: Rs. 2,250 / sq.ft

FINANCIAL & STATUTORY TAX SUMMARY

Constructed Built-up Area (SBA / BUA)	**1,800 sq.ft**
Package Quality Grade	**STANDARD Package**
Agreed Package Base Rate	**Rs. 2,250 / sq.ft**
Base Construction Cost (SBA × Rate)	**Rs. 40,50,000**
Applicable GST (18%)	**Rs. 7,29,000**
Grand Total Project Cost (Incl. GST)	**Rs. 47,79,000**
Effective All-Inclusive Cost per Sq.Ft	**Rs. 2,655 / sq.ft**

FLOOR-WISE AREA & ROOM DISTRIBUTION

#				
1	Ground Floor	630 sq.ft	900 sq.ft	4
2	First Floor	630 sq.ft	900 sq.ft	4

KEY MATERIAL QUANTITY TAKEOFF (IS 456 STANDARDS)

Material Category			
Fe 550D TMT Reinforcement Steel	High Ductility TMT (IS 1786)	6.30	Tonnes
Structural Grade Cement	53 Grade OPC / PPC (IS 12269)	756	Bags (50kg)
Manufactured Sand (M-Sand)	Zone II Coarse Aggregate Sand (IS 383)	3420	Cu.Ft
Coarse Aggregate (20mm & 10mm)	Crushed Blue Granite Metal	2430	Cu.Ft
Solid Concrete Blocks / Red Bricks	Class 3.5 MPa Load Bearing (IS 2185)	9360	Nos
Vitrified Flooring & Tiling	Double Charged GVT / Ceramic Tiles	2435	Sq.Ft

ENGINEERING ASSUMPTIONS & COMPLIANCE NOTES

1. Structural design conforms to IS 456:2000 (Plain & Reinforced Concrete) and IS 13920:2016 (Ductile Detailing of Reinforced Concrete Structures).
2. Safe Bearing Capacity (SBC) of soil is assumed at 180-200 kN/m². Extreme rocky excavation or deep pile foundation is subject to site geotechnical test.
3. All rates are inclusive of civil materials, labor, specialized formwork, batch mixing, vibrator compaction, and minimum 14-day curing protocol.
4. GST is computed at statutory rates (18%). Any statutory municipal sanction fees, betterment charges, or electricity/water board deposits are external.

Legal Notice: This document is an algorithmic quantity surveying estimate issued by Buildiqo.ai. Final contractor execution agreement may vary according to architectural drawings, structural engineering approvals, and site-specific conditions.